

Commissioning GFCA-Y2-A5

Part number: 8105388

FESTO



Data sheet

Feature	Value
Scope of services	Data backup and documentation Introduction to WebVisu software Configuration and parameterization System test Checking of electrical connections and of travel path Support with electric cabling On-site support during commissioning
Work involved on site	5 hours of work
Customer requirements	Qualified personnel responsible for the machine must be present on the agreed date YJKP kit must be assembled mechanically 24 V logic and 230/400 V load voltage must be made available Switch and Ethernet cable must be available
Provision of services	8-10 days subject to agreement