

Commissioning GFCA-Y2-A5-R

Part number: 8105389

FESTO



Data sheet

Feature	Value
Scope of services	Data backup and documentation Introduction to WebVisu software Configuration and parameterization Remote support during commissioning System test Checking of electrical connections and of travel path
Work involved on site	3 hours of work
Customer requirements	Qualified personnel responsible for the machine must be present on the agreed date YJKP kit must be assembled mechanically 24 V logic and 230/400 V load voltage must be made available Switch and Ethernet cable must be available Local installation of FFT-software (see Support Portal) Local administrator rights Local installation of TeamViewer or Bomgar communication software Stable internet connection
Provision of services	8-10 days subject to agreement